

What Does The Subaru P1490 Code Mean?

DTC <u>P0125</u>, <u>P0301</u>, P0302, <u>P0303</u> and <u>P0304</u> not set, ECT sensor less than 140°F and IAT sensor more than 50°F at startup, engine runtime over 10 minutes, and the PCM detected the ECT sensor signal did not reach 160°F under these engine operating conditions.

What Are The Potential Causes Of The Subaru P1490 Code?

- Check vehicle condition
- Check other DTC on display
- Check engine coolant
- Check radiator fan

Reference Sources

Subaru Impreza Repair Manual for P1490 - Pages 640-641.

